27	Labour charges for laying 1.1 KV class UG cable when supplied by agencies in existing trenches GI pipe / stoneware pipe/ on pole as required, Complete as per Specifcation	Mtr	150.00	5.50	Rupees Five and Fifty Paise Only
28	Digging of trench of 0.6m deep x 0.5m wide refilling the trench to the required level and consolidating etc., Complete as per Specifcation	Mtr	75.00	44.00	Rupees Forty Four Only
29	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class UG cable filled with neccesary bitumen / insulating compound complete with termiinalas, clamps, bolts, nuts, washers etc., Complete as per Specifcation	No.s	5.00	264.00	Rupees Two Hundred Sixty Four Only
30	Supplying and fixing of porcelain fuse channel with cut-out on existing / new wooden panel using neccesary nuts, bolts and washers etc., Complete as per Specifcation	No.s	30.00	440.00	Rupees Four Hundred Forty Only
31	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Asphalt surface road. Complete as per Specifcation	Cum	83.25	253.00	Rupees Two Hundred Fifty Three Only
32	Earthwork excavation for foundation of buildings water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods Complete as per Specifcation	Cum	416.25	227.88	Rupees Two Hundred Twenty Seven and Eighty Eight Paise Only
33	Providing and installing at site of work P.V.C pipees including cost of pipes and specials and labour including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not leass than 15 cms with gravel or selected earth available from the excavation etc., Complete as per Specifcation	Rmtr	1365.00	117.00	Rupees One Hundred Seventeen Only
34	Supplying and fixing 50 mm GI pipes 'B' class heavy duty Complete as per Specifcation	Mtr	50.00	325.00	Rupees Three Hundred
35	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m. Including cost of all labour Complete as per Specifcation	Cum	416.25	60.48	Rupees Sixty and Forty Eight Paise Only
36	Transportation of pumping machineries Complete as per Specification.	No.s	5.00	900.00	Rupees Nine Hundred Only
37	Erection of pumping machineries Complete as per Specifcation	No.s	5.00	900.00	Rupees Nine Hundred Only

Note: The said work for sanctioned estimate cost Rs.30.00 Lakhs (Rupees Thirty Lakhs Only) (Incl.10%+1%KRIDL Charges + 1% Quality control tests Charges) based On "Approved SR Rates"

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Received by